



ProgRama Part # 30185
Part # 163 830 0185
Brand Genuine
OE # 163 830 0185
Weight 1.2 lbs



Application Data:

1998 – 2003 Mercedes Benz ML320
 1999 – 2001 Mercedes Benz ML430
 2000 – 2003 Mercedes Benz ML55 AMG

Problem	Subject	Possible Solution
Insufficient Air Conditioning when idling	Model 163.154/172 up to VIN A289564 (Models ML320/ML430)	<ul style="list-style-type: none"> - Inspect fuse f44, replace if blown. - Check auxiliary fan operation. <p>[Note: If auxiliary fan does not operate, perform the corresponding diagnosis and repair. If the fan does not operate satisfactorily, check whether the auxiliary wiring harness for the auxiliary fan has already been installed. If auxiliary wire harness is already installed, ensure that a 40 Amp fuse is located at f44.</p>
<ul style="list-style-type: none"> - Defroster flap does not function correctly. - Rear air flap does not function correctly. - No air to the footwell. - Malfunction of recirculated air/fresh air flap. - Noise in the air/ heater housing. 	ALL Models	<p>Inspect the affected flap for a broken actuator lever and replace as necessary. Replacement actuator levers are available as a spare part.</p>

This unit has a 3 year warranty from the date of purchase.



ProgRama Inc
 3500 NW Boca Raton Blvd Ste. 501
 Boca Raton, FL 33431
 Tel: 561-338-8843 | Fax: 561-338-2400